INDIAN INSTITUTE OF TECHNOLOGY KANPUR INSTITUTE WORKS DEPARTMENT

QUOTATION

Sub: Providing copper plate earthing for laboratory machine to be installed at ground floor of block C at Old SAC building.

S.N.	Description	Qty.	Unit	rate without GST (Rs.)	Estimated Amount without GST (Rs.)
1	Earthing with copper earth plate 600 mm X 600 mm X 3 mm thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7 meter long etc. without charcoal/ coke and salt as required.		sets	12133.27	24266.54
2	Supplying and laying 25 mm X 5 mm copper strip at 0.50 meter below ground as strip earth electrode, including connection/ terminating with nut bolt, spring, washer etc. as required. (Jointing shall be done by overlapping and with 2 sets of brass nut bolt & spring washer spaced at 50 mm).		Mtrs.	852.26	8522.60
3	Providing and fixing 25 mm X 5 mm copper strip in 40 mm dia G.l. pipe from electrode including connection with brass nut, bolt, spring, washer excavation and re-filling etc. as required nut bolt, spring, washer etc. as required.		Mtrs.	1359.93	16319.16
4	Supplying and drawing following sizes of FRLS PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
b)	3 x 10 sq. mm	5.00	Mtr.	426.00	2130.00
		Estimated Amount (A)			51238.30

विनय कुमार तिवारी
(VINAY KUMAR TIWARI)
अधिशापी अभिवंता (वि॰एवं वा॰) E.E. (Elect & AC)
सं॰िन॰वि॰, भा०पो० संस्थान, कानपुर
I.W.D., I.I.T., Kanpur

Annexure A

Performa of Bid Security Declaration

(To be submitted by bidder on its Company Letterhead (scanned copy))